SAMPLE

TITLE

TECHNICAL RIDER (v *.*)

Author

TABLE OF CONTENTS

| PROJECT DESCRIPTION |
|---|
| ARTIST – CREDITS |
| PRODUCTION – CONTACTS |
| EQUIPMENT – CUSTOM MEDIA SERVER SYSTEMS |
| EQUIPMENT – POWER |
| EQUIPMENT – NETWORK |
| SYSTEM DIAGRAMS |
| TECH – SCHEDULE / CREW |
| TECH – REHEARSAL REQUIREMENTS |

PROJECT DESCRIPTION

https://vimeo.com/tml/ilya

"IL Y A" is a *membrane* video installation for an indoor, publicly accessible site in Montreal. The installation poetically mixes live video of the visitor with historical moving images from before living memory. The site and / or the historical footage should reference rhythmic laboring or pedestrian movement. Physically, the installation is a free-standing, bodyscale, double-sided video wall, with 12 channel sound.

(

WHY IS IT INTERESTING? Artistic significance Technical significance Social significance

PRIOR ART


)

ARTISTS & PRODUCTION CREDITS

| *** | Concept, Direction | |
|--------------|---|--|
| *** | Physical installation design, Fabrication | |
| *** | Realtime video, State logic | |
| *** | Sound design, programming | |
| *** | Production lead, design | |
| *** | 0 | |
| <u>ጥ ጥ ጥ</u> | Computer graphics | |
| *** | Realtime sound and video | |
| *** | Realtime video | |
| *** | State logic | |
| *** | Documentation, Lighting | |
| *** | Production, Documentation | |
| *** | Archival research | |
| | | |

•••

PHYSICAL INSTALLATION



Designed for museum and gallery exhibition, the physical installation is a rigid, opaque board mounted in a rigid aluminum frame. Each side has one video projector beaming an image onto that side. The projector clears the head of any visitor.


Height: 8'6" Installation footprint: 5' x 7' Weight (*excluding* computer gear in flight cases): 200 lbs

Shipped in wheeled, wooden crate: 88" x 39" x 74" tall, total weight: about 300 lbs.

EQUIPMENT – CUSTOM MEDIA SERVER SYSTEMS

PROVIDED BY ARTIST

Media Servers secured in Professional 20" Shock Rack Cases with rolling casters,



performances.

AUDIO EQUIPMENT - Rack Mounted

| 1 each | Motu 828MK2 - Firewire Audio Interface | |
|--------|---|--|
| 1 each | Presonus Digimax FS – Audio Interface - 8 Channel Microphone Preamp | |
| 1 each | Russound R1250MC – Audio Power Amplifier | |
| 1 each | Furman PL-8 Series II – Power Conditioner | |

COMPUTER EQUIPMENT - Rack Mounted

| 1 each | Apple Mac Mini – Desktop Computer |
|--------|-----------------------------------|
|--------|-----------------------------------|

| 1 each | Apple Mac Pro – Computer Workstation |
|--------|--|
| 1 each | LCD Computer Monitor w/ keyboard and mouse |

VIDEO SIGNAL DISTRIBUTION

| 2 each | Geffen VGA Extenders - Receivers |
|--------|---|
| 2 each | Geffen VGA Extenders - Senders |
| 1 set | Geffen USB 2.0 Extenders Sender Receiver Pair |
| 1 each | Matrox Triple IHead2Go Digital Edition |

VIDEO PROJECTORS - DIRECT ATTACHED TO SCREEN FRAME

| 2 each Epson PowerLite 460W XGA Multimedia Projectors | 2 each | Epson PowerLite 460W XGA Multimedia Projectors | |
|---|--------|--|--|
|---|--------|--|--|

AUDIO SPEAKERS - AMBIENT SOUND

| 2 pair | KEF Satellite Audio Speakers |
|--------|------------------------------------|
| 1 each | KEF Kube-1 Audio Speaker Subwoofer |

AUDIO SPEAKERS - DIRECT ATTACHED TO SCREEN FRAME

8 each Boston Acoustics Satellite Speakers

TRANSPORT CASES

- 1- ATA flight case 28' x 29.50' x 29.50': video gear
- 1- ATA flight case 28.25' x 29' x 26.25': sound gear
- 2- self packed boxes 19' x 12.2' x 8': Bose speakers
- 1- self packed box 16.8' x 16.2' x 17.2': KEF speakers


EQUIPMENT – POWER

3 each dedicated circuits **provided by the Venue**:

- 15 AMP for Video Media Server Rack Unit
- 15 AMP for Sound Media Server Rack Unit
- 15 AMP for Video Projectors


EQUIPMENT – NETWORK

Unfiltered Broadband Internet connection **provided by the Venue**.




SYSTEM DIAGRAMS


Video – Display




Video - Camera Data Acquistion



Network



Physical Link



MAC:

TECH – SCHEDULE / CREW

SAMPLE SCHEDULE

| Day | Calls | Technician Requirements |
|--------|--------------------------------------|--|
| Day 0 | | Required power and network services delivered to site. The following items are to be delivered to space prior to artist arrival: <u>Worktables, power strips</u> <u>+extensions,</u> |
| Day 1 | 10am–7pm ARTIST LOAD-IN and SETUP | ARTIST plus 2 technicians from <i>II y</i> <i>a</i> team. Assembling main structure needs 4 people for 1 hour. |
| Day 2 | 10am-7pm TECHNICAL REHEARSAL. | ARTIST plus 1 technician from <i>II y a</i> team. |
| Day 3 | Installation OPEN S | Gallery assistant to supervise installation. |
| Strike | 4 hours | 1 <i>II y a</i> team member. Plus one hour with 3 assistants to disassemble and pack main frame, and 1 assistant for remaining time. |

TECH – REHEARSAL REQUIRMENTS

All cases and parts are designed to fit through standard interior single-width doorways. Ramp access would be convenient.

PROVIDED BY VENUE (Day 1 and Day 2)

- 2 Working tables
- 3 Chairs
- 2 power strips and extra extension cords
- 2 table lamps
- Wireless Internet Access

Physical, secure access to space, as many hours per day as possible,

e.g.: 10 hours / day x 2 days.

PRODUCTION – CONTACTS

| | *** | 650-815-9962 (USA) |
|---------------|-----|-----------------------|
| DIRECTOR | | 514-817-3505 (Canada) |
| San Francisco | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| Montréal | | |
| | | |
| | | |
| | | |
| | | |
| | | |